


How to operate Spectrometer and Dump safely ?

TTF2 Review Meeting in Salzau, 20-23. Jan. 2003, M. Schmitz -MIN-

- A. Overview, General Information**
- B. Information on special Components**
- C. Philosophy of Optics & Layout**
- D. Status, Time Schedule**
- E. Questions, Next Steps**

A: Overview



A: General Information

Tasks of this Section

1.) Spectrometer,


- measure energy with accuracy of:
 relative energy spread $(\Delta p/p)_{\text{rel}} \leq 1 \cdot 10^{-4}$
 absolute energy measurement $(\Delta p/p)_{\text{abs}} \approx 1 \cdot 10^{-3}$
- momentum acceptance $(\Delta p/p)_{\text{max}} \geq \pm 3\%$

2.) Beam Dump, i.e. absorb beam with:

- beam energy $E_0 \leq 1.6 \text{ GeV}$
- bunch train population $N_t \leq 4 \cdot 10^{13} \text{ e-}$
- bunch train repetition $\nu_t \leq 10 \text{ Hz}$
 \Rightarrow average beam current $I_{\text{ave}} \leq 64 \mu\text{A}$
 average beam power $P_{\text{ave}} \leq 102 \text{ kW}$
 energy per bunch train $W_t \leq 10.2 \text{ kJ}$

Geometry of this Section



- 7° tilt of deflection plane wrt. vertical plane
- $19^\circ = 331.6 \text{ mrad}$ deflection angle of dipole
 $\Rightarrow D(s) \approx s/3$ (s: drift space behind dipole)



- main axes of components in beam line
 \parallel and \perp wrt. deflection plane
- quite „crowded“ region,
 3 beam lines close together

B: Absorber

- re-use old TTF1 dump and modify by:
 - 40cm front part extension**
 - ⇒ average heating in Al reduced
 - slow beam sweeping** $r_{slow} = 2\text{cm}$
 - ⇒ average heating in C and Al reduced
 - beam spot at dump entrance $\sigma_x \cdot \sigma_y \geq 1\text{mm}^2$
 - ⇒ instantaneous heating in C max. $\approx 250\text{K}$
 - max. temperatures just after bunch train
 - in graphite $\leq 400^\circ\text{C}$ (+200K w/o sweep)
 - in aluminum $\leq 250^\circ\text{C}$
 - dump operates at normal atmosphere
 - design on basis of 2GeV / 130kW
 - ⇒ limit for P_{ave} at const. power density:
- | | | | | | |
|-------------------------|-----|-----|-----|-----|-----|
| E_0 [GeV] | 0.4 | 0.8 | 1.2 | 1.6 | 2 |
| limit of P_{ave} [kW] | 87 | 108 | 120 | 125 | 130 |
- 2 (1 + 1 spare) modified absorbers ready
 - 1 absorber is installed in place



B: Beam Exit Window (1)

1.) General Design Concept (M. Maslov, Protvino)

- C-Ti-C sandwich
 Ti: + for cyclic stress & vacuum tight, bad thermal conductor
 C: supports Ti and transports heat to external cooling
- Limits: $(\Delta T_{inst})_{max} \leq 250K$ in Ti, $T_{abs} \leq 400^\circ C$ in C & Ti

2.) Instantaneous Heating

$$(\Delta T_{inst})_{max} = \frac{1}{\rho} \frac{dE}{dz} \cdot \left(\frac{dN}{dA}\right)_{max} \cdot \frac{1}{c}; \quad \left(\frac{dN}{dA}\right)_{max} = \frac{N_i}{2\pi \cdot \sigma^2}$$

lower limit of spot size at window with factor 5 safety

$$\Rightarrow (dN/dA)_{max} \leq 1.3 \cdot 10^{12} \text{ e-/mm}^2 \Leftrightarrow \sigma_x \cdot \sigma_y \geq 5\text{mm}^2$$

3.) Equilibrium Heating


a) with 2cm sweep
$$(\Delta T_{eq})_{max} = \frac{1}{\rho} \frac{dE}{dz} \cdot \rho \cdot \frac{I_{ave}}{e} \cdot \frac{1}{2\pi \cdot \lambda} \cdot \ln\left(\frac{R_{window}}{R_{sweep}}\right)$$

b) without sweep
$$(\Delta T_{eq})_{max} = \frac{1}{\rho} \frac{dE}{dz} \cdot \rho \cdot \frac{I_{ave}}{e} \cdot \frac{1}{4\pi \cdot \lambda} \cdot \ln\left(1 + \frac{(R_{window})^2}{2 \cdot \sigma^2}\right)$$

* \Rightarrow good thermal contact between Ti-C important

	$(\Delta T_{inst})_{max}$ [K]		$(\Delta T_{eq})_{max}$ [K]			Power dissip. [W/mm]
	5mm^2	1mm^2	with sweep	without sweep		
σ^2				5mm^2	1mm^2	
C	39	195	41	109	139	16.3
Ti	57	285	(444)*	(1190)*	(1500)*	43.2

* assumes no heat transfer to C




	ρ [g/cm ³]	c [J/(g·K)]	λ [W/(m·K)]
C	1.7	0.8	70
Ti	4.5	0.55	17


B: Beam Exit Window (2)

4.) DESY exit window construction (T. Wohlenberg)

- take geometry from Protvino design, but braze Ti and C instead of pressing
 - pressed: $\approx 0.14 - 0.25 \text{ W}/(\text{cm}^2 \cdot \text{K})$
 - brazed: $\geq 0.8 \text{ W}/(\text{cm}^2 \cdot \text{K})$
 - \Rightarrow improved and long term stable thermal contact
- all brazing pre-tests were successful
- construction finished
- all parts manufactured for 2 windows
 - \Rightarrow brazing of 1. final window starts now
- venting the small volume between dump and window with dry nitrogen gas, $\approx 1-10 \text{ l/day}$
 - \Rightarrow protection of atmosphere side of window against aggressive substances like ozone or NO_x
- 1 complete Protvino window is at DESY and serves as fall back solution



C: Layout



Layout Goals + Given Space
 =>
Position of Components
No Room to Play !

C: Layout Goals

1.) Dispersion at Diagnostics: No Quad Influence & as Large as Possible

⇒ **diagnostics in drift as far as possible from D6DUMP**

$$\text{OTR res.} \geq 50\mu\text{m} \ \& \ (\Delta p/p)_{\text{rel}} \leq 1 \cdot 10^{-4} \rightarrow D_{\text{OTR}} \geq 0.5\text{m} \Leftrightarrow s \geq 1.5\text{m}$$

2.) Momentum Acceptance $\geq \pm 3\%$ ⇒ Dispersion limiting Quad Q10DUMP as close as possible to D6DUMP

$$45\text{mm aperture radius} \rightarrow D_{\text{max}} \leq 45\text{mm}/3\% = 1.5\text{m} \Leftrightarrow s \leq 4.5\text{m}$$



3.) Beam Conditions at Window:

a) $D \approx 0$ (beam pos. independent of dipole variation)

b) $(dN/dA)_{\text{max}} \leq 1.3 \cdot 10^{12} \text{ e-/mm}^2$ (inst. heating)

⇒ **2 large apert. Quads Q10DUMP & Q11DUMP behind diagnostics**

use **QC**: bore $\varnothing=100\text{mm}$, $l_{\text{iron}}=1\text{m}$, $I_{\text{max}}=350\text{A}$, $(k \cdot l)_{\text{max}}=2.76/\text{m}$ @1.6GeV/c

4.) Pure Drift $\geq 2.5\text{m}$ between Sweeper and Dump ⇒ Sweeper is last Magnet


5.) Dispersive Behaviour of Spectrometer (except sign) independent of

whether the beam comes from EXP or BYP

⇒ **1 Quad Q4DUMP exactly between D1DUMP and D6DUMP**

requires **fixed strength** of $k \cdot l = 0.83/\text{m}$ $\Leftrightarrow g \cdot l = 5.6\text{T}$ @2GeV/c

use **TQF**: bore $\varnothing=70\text{mm}$, $l_{\text{iron}}=340\text{mm}$, $I_{\text{max}}=250\text{A}$, $(g \cdot l)_{\text{max}}=6.38\text{T}$



6.) β -Focus at OTR at least in dispersive plane, required only during $\Delta p/p$ measurement at reduced N_t !

C: Optics Philosophy

- Q10/Q11DUMP should also have fixed strength (like Dipoles, Sweeper and Q4DUMP)
 ⇒ **Field of all Spectrometer Magnets scales linear with Momentum**

• 2 Operation (Optics) Modes

Mode A: Full Intensity Mode without OTR screen measurement requires

A1 a: D(window) ≈ 0m, b: D(D6DUMP) = 0m & D'(D6DUMP) = -D'(D1DUMP) b) is task of Q4DUMP

A2: $(\beta_x \cdot \beta_y)^{0.5} \approx 8000\text{m}$ at window, because $\left(\frac{dN}{dA}\right)_{\max} = 1.3 \cdot 10^{12} \frac{e}{\text{mm}^2} \geq \frac{N_t}{2\pi \cdot \sigma_x \cdot \sigma_y} \Rightarrow \sqrt{\beta_x \cdot \beta_y} \geq \frac{N_t \cdot \gamma}{2\pi \cdot \epsilon_n \cdot \left(\frac{dN}{dA}\right)_{\max}}$
 for $\epsilon_n = 2 \cdot 10^{-6}\text{m}$, $\gamma = 3200$ (1.6GeV/c), $N_t = 4 \cdot 10^{13}$

Mode B: OTR $\Delta p/p$ Measurement, few bunches → N_t strongly reduced (e.g. 30 bunches = $30 \cdot 4nC = 7.5 \cdot 10^{11}$)

B1: same as A1)

B2: $(\beta_x \cdot \beta_y)^{0.5} \approx 150\text{m}$ at window, for $\epsilon_n = 2 \cdot 10^{-6}\text{m}$, $\gamma = 3200$ (1.6GeV/c), $N_t = 7.5 \cdot 10^{11}$

B3: beam size at OTR must be dominated by dispersion, i.e. $D_{\text{OTR}} \cdot (\Delta p/p)_{\min} \gg \sqrt{\beta_{\text{OTR}} \cdot \epsilon_n / \gamma}$
 ⇒ **$\beta_y \approx 0.1\text{m}$ at OTR, for $D_{\text{OTR}} = 0.8\text{m}$, $\Delta p/p = 10^{-4}$, $\epsilon_n = 10 \cdot 10^{-6}\text{m}$, $\gamma = 400$ (200MeV/c)**

• Optics at the output of EXP or BYP has to be adjusted, in order to fulfill Mode A or B

beam from EXP: optics calc. (M. Koerfer) show feasibility

Q10: $k \cdot l = \text{const} = -1.04/\text{m}$, Q11: $k \cdot l = \text{const} = +2.68/\text{m}$!

→ more detailed studies necessary:

e.g. beam from BYP, tolerances wrt. energy- and optic-error

	at OTR		at window		
	β_x	β_y	β_x	β_y	D [m]
Mode A	90 m	300 m	≈ 8000 m		≈ 0
Mode B	≈ 0.2 m		≈ 2000 m		

D: Status (1)

SUPPORTS

Region D1Dump to D6Dump

- construction not finished, expected by end feb.02

Region D6Dump to Q10Dump, i.e. Diagnostics Area

- construction not yet started ! → perhaps need help here
expected start mid feb.03,
but overlap with DESY shut-down activities

Q10&11Dump

- construction finished end aug.02
- both supports are manufactured and at DESY

Region RD13Dump to Exit Window

- construction almost finished
completion expected by mid feb.03

MAGNETS

- all magnets are at DESY (TDC, QC, TQF, mod. HSK, CV)
- alignment of survey marks wrt. poles: TDC, CV to be done
- B-measurements finished by end of feb.03

DIAGNOSTICS

OTR, (SCREEN/9Dump)

- chamber ready and cleaned
- 2 opt. windows NW100 exist
- mover & opt. system not ready yet

Stripline BPM, (BPM/9Dump)

- complete unit (+2 bellows) from TTF1 exists

Button BPM's, (BPM/5&15Dump)

- chambers constructed (→ remaining vac. syst)
order for manufacturing pending
- delivery buttons beg. mar.03

TOROID, (Toroid/8Dump)

- chamber construction ready
manufacturing status ?

SEM, (Sem/8Dump)

- installation not decided
- chamber exists from TTF1
but grid may be modified (45°, 2 planes)
- dummy chamber is foreseen alternatively

D: Status (2)

VACUUMCHAMBERS (except Diagn)

for D1&6DUMP, TDC

- construction finished jun.02
- presently manufactured at FMB (Berlin)
- delivery expected end jan.03

EXIT WINDOW


- first DESY window expected mid mar.03
- Protvino window exists at DESY since feb.02

Remaining SYSTEM

- construction of all chambers finished end nov.02
- order for manufacturing pending

ALL vacuum parts must undergo special cleaning procedures

DUMP section has to fulfill standard: „particle-free“



D: Status (3)

associated with ext. costs not yet approved

Rough Schedule, Status:Jan03 Section: TTF2-DUMP,	JAN 03	FEB 03	MAR 03	APR 03	MAY 03	JUN 03	JUL 03
SUPPORTS							
Region D1Dump to D6Dump	construction		manufacturing		install in tunnel		
Diagnostics Region !		construction		manufacturing		install in tunnel	
Q10&Q11Dump					install in tunnel		
Region RD13Dump to Exit Window	construction		manufacturing		install in tunnel		
MAGNETS							
B-measurements	install chamber (see chamber)					install in tunnel	
align survey. marks							
VACUUMCHAMBERS (except Diagn.)							
for TDC	manufacturing	clean & vac. test					
for Q10&Q11Dump		deinstal	clean & vac. test				
for Q4Dump and RD13Dump		manufacturing		clean & vac. test			
remaining chambers		manufacturing			clean & vac. test		
Exit Window	manufacturing 1. window		clean & vac. test				
DIAGNOSTICS							
OTR (Screen/9Dump) chamber mover & screen ? optical system ?	clean & vac. test						
Stripline BPM (BPM/9Dump)		clean & vac. test					
Button BPM's (BPM/5&15Dump)		manufacturing		clean & vac. test			
Toroid, (Toroid/8Dump) ?							
SEM, (Sem/8Dump) ?							

D: Questions, Next Steps

Main Questions

- How are we really sure that the **beam size at the window is not too small** ?
 - rely on optics and magnet settings
 - measure window temperature at position of beam by IR-radiation



- How are we really sure that the **beam is cleanly guided to the dump** ?
 - BPM's (BPM/15Dump directly in front of exit window)
 - beam loss detection in combination with dedicated limiting apertures

Next Steps

- Work on optics
- Concentration on controls