

Technical Goals of the Collaboration

Infrastructure in US

SMTF Deliverables

- Common goals for all projects
- Project specific technical goals
 - ILC, PD, CW, RIA...others
- Infrastructure in US labs
- SMTF Deliverables
- Conclusions

Establish Overall Infrastructure for all projects

- Establish SMTF Infrastructure in Meson Hall & New Meson for ILC, PD, CW, and RIA Activities
 - Cryomodule test areas
 - Beam test areas
 - Cavity test areas (in later phases)
 - Cryogenics,
 - Phase I & II : 60 W at 2 K initial (refrigerator exists), Additional cryo at 4K
 - Phase III: 300 W at 2 K later, 300 W at 4 K, 5 kW at 40 K
 - RF
 - Phase 1- one 15 MW modulator (B1), one 5 MW klystron
 - Phase 2- one 15 MW modulator (B1), one 10 MW klystron
 - Phase 3- two 15 MW modulators (one new B3), two 10 MW klystrons (one new)
 - Shielding....

SMTF Meson area picture

Meson East & SM12 magnet 20April2005
picture

Also under consideration:
New Muon Facing South

picture

ILC - (1) Acquire Cavities and Cryomodules

- Enhance infrastructure for cavity treatment and testing at collaborating institutions, Fermilab and industries.
 - e.g. Jlab EP 9-cell cavities, vert test 9-cell cavities
 - e.g. Complete cavity treatment facility at Argonne/Fermilab
- Establish process for repeatable high performance (35 MV/m, $Q > 10^{10}$) with 9-cell cavities
- Acquire Cavities and cryomodule components for SMTF
 - Fabricate 1.3 GHz high gradient cavities, cavity-strings and prototype cryomodules in collaboration with laboratories, universities and US industrial partners.
 - Acquire DESY cryomodule
- Develop design for 4th generation cryomodule in concert with ILC labs world wide
- Acquire 4th generation cryomodule components, assemble 6

ILC (2) Cryomodule Assembly and Test

- Establish infrastructure for assembly of prototype cryomodules using cavities or cavity-strings produced at collaborating institutions and industries.
- Acquire, assemble and test RF components
- Establish cryomodule test area in Meson Hall
- Test cryomodules on module test stand

ILC - (3) Beam Tests

- Move FNPL injector to Meson Hall
 - Upgrade Injector
- Test modules with beam
- Demonstrate 1.3 GHz cavity operation at 35 MV/m with beam currents up to 10 mA at a 0.5 % duty factor.
- Measure key performance aspects
 - Long term operation, trip rates, recovery times, dark current, amplitude & phase control, alignment, vibration, input coupler performance, HOM damping...
 - Many long lists, with items to cover R1, R2, R3 and R4

More Detail : Technology Studies

- Determine the maximum operating gradient of each cavity & its limitations.
- Evaluate gradient spread and its operational implications.
- Measure dark currents, cryogenic load, dark current propagation, and radiation levels.
- Measure alignment of the quadrupole, cavities and BPM in-situ using conventional techniques (e.g. wire or optical).
- Measure vibration spectra of the cryomodule components, especially the quadrupole magnet.
- Measure system trip rates and recovery times to assess availability.
- Develop LLRF exception handling software to automate system and reduce downtime.
- Evaluate failures with long recovery times: vacuum, tuners, piezocontrollers, and couplers.


More Detail : Physics Measurements

- Beam energy: a spectrometer would provide an independent and accurate measurement of the accelerating gradient (rf based techniques are not as accurate).
- Long-range wake-field characterization: Measure frequency spectra of bunch positions downstream of cryomodule to search for high Q cavity dipole modes that could cause beam break-up in the ILC. Correlate these data with HOM power measurements.
- Tests of low-level rf system: demonstrate that a $< 0.1\%$ bunch-to-bunch energy spread can be achieved in a 1 msec bunch train.
- Impact of the SCRF cavity on transverse beam dynamics: measure the beam kicks caused by the fundamental mode fields.
- Study beam centering based on HOM dipole signals.

ILC - (3)

- Develop industrial production capability
- Work with industry to reduce costs
- Warren will discuss possible paths

Phases of SMTF Beta=1 Modules



Proton Driver

- The Proton Driver is an 8 GeV SCRF proton linac
 - For Neutrino Super-Beams & other new capabilities at FNAL
- The last 85% of the PD linac (1 GeV to 8 GeV) is *identical to the ILC*.
- Thus, R&D program for the *back end* of the Proton Driver is identical to the ILC SMTF synergy.
- R&D for the *front end* of the PD extends technology of SNS, RIA, JPARC, ILC, and other projects.

PD

- Establish area for high power, 325 MHz, testing of < 1 accelerator structures in pulsed mode ($\sim 1\%$ duty factor).
- Fabricate test structures and associated cryomodules
 - 325 MHz cavities in various beta ranges
 $= 0.47$ and 0.61 , 1300 MHz elliptical cavities
- The Proton Driver also uses $= 1$, 1.3 GHz cavities cryomodules that are nearly identical ILC.
 - Demonstrate operation of 1.3 GHz cavities and module at 27 MV/m with beam currents up to 8 mA at 0.75 % duty factor with multiple cavities being driven by one klystron using fast ferrite phase shifters.
- Demonstrate 1.3 GHz, ~ 0.5 -0.8, elliptical cavity operation at > 15 MV/m at $Q > 5 \times 10^9$ and a 1% duty factor with multiple cavities being driven by one klystron using fast ferrite phase shifters.
- Demonstrate high gradient operation in pulsed mode of 325 MHz, < 1 cavities and cryomodules.
- Demonstrate individual cavity resonance control with multiple cavities driven from one klystron, using fast ferrite phase shifters, at both 1.3 GHz and 325MHz
- Prototype new generation modulators
 - 3 ms pulse width beam pulse, rf pulse 4.5 ms
- Need time scale plan for building and testing

CW for Future Light Sources

- Establish a beam test area using ≈ 1 pulsed test beam.
- Fabricate high Q accelerating cavities and cryomodules
- Fabricate deflecting cavities and cryomodules
 - Also supports ILC crab cavity development elsewhere.
- Demonstrate 20 MV/m CW cavity operation with Q values of $\sim 3 \times 10^{10}$ with associated RF controls.
- Demonstrate wakefield suppression,. HOM absorbers
- Solve heat load management
- High stability and control of accelerating fields, goals of phase error $< 0.01^\circ$ and amplitude error $< 10^{-4}$
- Demonstrate deflecting cavities at transverse kick voltage of 5 MV/m, and $Q_0 > 5 \times 10^9$
 - HOM (higher-order modes) and LOM (lower-order modes) damping validation, polarization control

RIA

- The U.S. Rare Isotope Accelerator Project will include the construction of nearly 500 superconducting cavities of as many as 10 different types to accelerate ions over a velocity range $0.02 < \beta < 0.85$.
- Cavity types, cryomodules, couplers, and tuners are similar in design to PD

RIA

- Spokes are well developed technology but not tested with high power and not tested with beam
- Expand on-going RIA work
- Bare cavity tests, string assembly, module assembly
- ##Example resonator that needs to be developed
 - Improved design.
- Test modules
- First beam tests with significant beams via PD front end
- Higher power couplers than before

Accelerator Physics R&D

- Construct and operate the improved photo-injector
- ##Parameter Table of existing injector /compared to Table for upgraded injector/ILC parameters needed
- Beam test modules
- Long range and short range wakes, HOM load performance..
- 1 GeV upgrade injector would provide beam parameters similar to ILC injector useful for optimization studies
- Produce positrons, study beam dynamics of positron source, capture, matching, optimization
- R&D on beam instrumentation, beam diagnostics
- Train accelerator scientists.

Supporting SRF R&D

- High gradient and high Q R&D
 - Understand and improve processing steps
- Material research to improve cavity performance.
- In collaboration with partners
 - Applied Superconductivity Center, Wisconsin, Northwestern University
- Important R&D not pursued elsewhere
 - Dynamics of magnetic flux penetration into superconductors
 - Atom by atom analysis of niobium surface from oxide, to oxide interface, to metal

Existing Facilities

- Substantial facilities exist in US for
 - Cavity fabrication, preparation and testing
 - Cavity string and cryomodule assembly and testing
- Argonne, Cornell, Fermilab, Jlab, LANL,MSU
- These facilities will need enhancement to deal with challenges of
 - ILC level high performance
 - Support development of US industrial base
 - Large Scale Industrialization

Argonne

Phase I: The Joint ANL/FNAL Chemistry Facility






Chemical Processing Rooms

- Two sealed chemistry areas, 16 ft ceiling
- Large air scrubber suitable for RIA cavity production



Air Scrubber


Techniques: Clean Processing for SRF Cavities



Cornell

SRF Infrastructure


Deep Drawing



1000 Sq Ft Clean Room



Ebeam Welding



Chemical Etching



High Pressure Rinsing





Cornell
Cavity
Test Pits
(3)

Test Stand Ready for 9-cells



Jlab

Production Facilities – Cavities



Deep Drawing Press



Electron Beam Welder



1250°C Vacuum Oven



Closed Chemistry Cabinet



Electropolish Cabinet




Hi Pressure Rinse Cabinet



Class 100 & 10 Clean Rooms

Production Facilities – Cryomodules



Operated by the Southeastern Universities Research Association for the U.S. Department of Energy


Thomas Jefferson National Accelerator Facility

System Tests at JLab - Funk

Page 8



Production Facilities - Testing




- VTA has 500 W cw sources at 805 and 1497 MHz
- CMTF has 20 kW 805 MHz cw source and 16 kW 1497 MHz cw source



LANL

Facilities at the SRF Lab

2600 ft² class-100 Clean room, 10-ft high



Ultra-pure water with 2000 G/day and 1500 G storage tank



140 ft.

cryostat inserts



Cryostats with movable radian shield



High-pressure rinse in a clean room. NL capabilities for the ILC Building MPF-17



Control, tuning



This 2,600 ft² (260 m²) clean room

38-inch ($\sim 1\text{m}$) diameter, 10-ft ($\sim 3\text{m}$)
deep cryostat with radiation shield



11/15/04


LANL capabilities for the ILC

12

industrialization

43m


30m



11/15/04


LANL capabilities for the





Existing vertical cryostat with 8 TESLA 9-cell cavities in it, which enables us to test 8 cavities by filling the cryostat with liquid helium only once

MSU



Deliverables

- Repeatable process for 35 MV/m, high gradient, high Q, 9-cell cavities
- US - ILC 8-cavity cryomodule
- 4th generation cryomodule
- R1, R2 cavity, cryomodule and beam test goals
- 3rd harmonic cavities for injector
- Deflecting cavity for beam diagnostics and crab
- Fast ferrite based tuner for ILC
 - Match cavity to gradient
 - Improve coupler conditioning times

Conclusions

- Several ambitious SRF-based accelerator projects are planned in US
 - International Linear Collider, Light sources, RIA, PD
- SMTF will expand existing srf expertise at: Argonne, Cornell, Fermilab Jefferson Lab, MSU
- SM&TF will provide:
 - a facility where different module types & linac systems can be tested (beam)
 - a collaboration on cold linac technology, module development & fabrication
- SM&TF will allow US to:
 - Take advantage of advances in technology to extend science goals
 - Pursue potential of SRF
 - Minimize cost of new projects by using most advanced SRF methods
 - Build cooperation with industry
- –Collaborate with Europe and Asia
- Overlap of national experts at one facility will allow exchange of ideas and thus unify US approach to SRF-for more effective use of resources
- Build collaboration to prepare/plan to host ILC & build fraction of linac in US (under direction of ILC- GDE)